



April 18, 2023

To: All Potential Bidders

From: Kelly Vu, Business Services Supervisor

Re: Addendum #1, RFP # PL-04-23

The purpose of this addendum is to revise the components of the Request for Proposal (RFP) for Pacific Amphitheatre Lighting Equipment and Services. All terms and conditions of the original RFP remain unchanged.

---

Document to be revised as follows:

## 1. RFP, PART V, STATEMENT OF WORK (SOW) TO BE PERFORMED

Page 22, Section G. 3. TRUSSING

Original: 3.

### TRUSSING

Trusses are flown from the existing super structure. The below list is representative of what would be expected, but is dependant on the specifics of the Bidder's lighting design:

- (15) Tomcat 20.5" x 10' Truss
- (24) Total Structures 12"x12"x10' truss for cable bridge and US truss 1, 2 SL & SR wings & Sponsorship logo banner
- (5) 10' Ladder beam rag truss sections

Contractor must provide the following equipment and install District-provided sponsorship banners and sound wall curtains:

- (16) 12" x 12" x 10' box truss, medium duty, black
- (1) 12" x 12" x 5' box truss, medium duty, black

New: 3.

### TRUSSING

Trusses are flown from the existing super structure. The below list is representative of what would be expected, but is **dependent** on the specifics of the Bidder's lighting design:

- (15) 10' Tyler GT truss black w/pins & wheels (downstage, mid-stage and upstage truss)
- (1) 50' medium duty 20.5" truss black with bolts (upstage video and curtain truss)
- (1) 30' medium duty 12" truss black with bolts (cable bridge)
- (1) 40' medium duty 12" truss with black bolts (upstage #2 truss)
- (2) ½ ton CM hoists with all required rigging per point
- (16) 1-ton CM hoists with all required rigging per point

### Curtain and banner rigging

- (2) 50' medium duty 12" truss black with bolts (side curtains)
- (1) 65' light duty 12" truss black with bolts (banner truss)

- (6) ½ ton CM hoists with all required rigging per point (side curtains)
- (4) ¼ ton CM hoists with all required rigging per point (banner truss)

Contractor must provide the following equipment and install District-provided sponsorship banners and sound wall curtains:

- ~~(16) 12" x 12" x 10' box truss, medium duty, black~~
- ~~(1) 12" x 12" x 5' box truss, medium duty, black~~

## 2. RFP, PART V, STATEMENT OF WORK (SOW) TO BE PERFORMED

Page 23, Section G. 5. CONTROLLERS

Original: 5.

Control position is Front of House (FOH) adjacent to audio.

Due to show requirements, two (2) consoles are required. This combination has been successfully utilized in the past:

- Grand MA 2 Lite Lighting Console w/ PC backup with Command and Fader wings
- Grand MA 2 PC with MA Fader Wing and MA Command Wing for redundancy

Control cables from FOH to dimmer world will be run through the Pacific Amphitheatre conduit system.

New: 5.

Control position is Front of House (FOH) adjacent to audio.

Due to show requirements, two (2) consoles are required.

- Grand MA3 Full Lighting Console
- Grand MA3 Lite Lighting Console

Control cables from FOH to dimmer world will be run through the Pacific Amphitheatre conduit system.

## 3. RFP, PART IX, FORMS SECTION

Page 35, Form A-3, FINANCIAL PROPOSAL BID FORM

Financial Proposal Bid Form updated to reflect changes to Part V, Page 22, Section G.3. and Page 23, Section G.5.

All other terms and deadlines remain unchanged.

To comply with the Addenda (Addendum) requirements we are asking that bidders to either reply to this email such as "Received RFI #1, Addendum #1" or acknowledge on the Financial Proposal Bid Form on the right hand corner with "Received RFI #1, Addendum #1". We will consider both options as confirmation.

Thank you.

*-End Addendum #1-*