

03-131-4113 & 03-131-4114
Grid 77-19B

PERMIT

COMMONWEALTH OF VIRGINIA
DEPARTMENT OF HEALTH


THIS PERMIT
EXPIRES ON

DATE OF ISSUE

12/06/04



OPERATOR: Franklin D. & Evelyn D. Forquer
ADDRESS: 115 Halls Store Road
Willis, VA 24380



The above operator has made application and in accordance with the regulations of the Board of Health of the Commonwealth of Virginia is authorized by the **Floyd County** *Health Department*
to operate a **Sewage disposal system**


HEALTH OFFICIAL

THIS PERMIT IS NOT TRANSFERABLE FROM ONE INDIVIDUAL OR LOCATION TO ANOTHER

SHEET 2

Water Supply and/or Sewage Disposal System Construction Permit

Commonwealth of Virginia
Department of Health

Health Department
Identification Number
Map Reference

FLO/D 00 Health Department

77-19-B

General Information

Water Supply System: New ☒ Repair ☐ Public ☐ FHA ☐ VA ☐ Case No. ☐
Sewage Disposal System: New ☒ Repair ☐ Expanded ☐ Conditional ☐ Public ☐
Based on the application for a sewage disposal system construction permit filed in accordance with Section 2.13 E, of the Sewage Handling and Disposal Regulations and/or Section 2.13 of the Private Well Regulations a construction permit is hereby issued to:
Owner FRANKLIN D. & EVELYN D. FORQUER, JR. Telephone 593-3303
Address 115 HALLS STORE RD, WILLIS, VA 227 For a Type I Sewage Disposal System or Well to be constructed on/at INTERSECTION RTE 799 & 604 ON 604 FOR 1/2 MILE ON RIGHT
Subdivision ☐ Section/Block ☐ Lot ☐ Actual or estimated water use 150

DESIGN

NOTE: SEWAGE DISPOSAL SYSTEM INSPECTION RESULTS

Water supply, existing: (describe) TO BE DRILLED BETWEEN THE TWO CABINS
To be installed: class III C PRIVATE
cased 20' grouted 20'

Water supply location: Satisfactory yes ☐ no ☐
comments
Completion Report
G. W. 2 Received: yes ☐ no ☐ not applicable ☐

Building sewer:
3" / 4" I.D. PVC Schedule 40, or equivalent.
Slope 1.25" per 10' (minimum).
☐ Other

Building sewer: yes ☐ no ☐ comments
Satisfactory NOT INSTALLED
10-22-03

Septic tank: Capacity 1,000 gals. (minimum).
☒ Other WITH INSPECTION PORT

Pretreatment unit: yes ☒ no ☐ comments
Satisfactory

Inlet-outlet structure:
PVC Schedule 40, 4" tees or equivalent.
☐ Other

Inlet-outlet structure: yes ☒ no ☐ comments
Satisfactory

Pump and pump station:
No ☒ Yes ☐ describe and show design.
if yes:

Pump & pump station: yes ☐ no ☐ comments
Satisfactory N/A

Gravity mains: 3" or larger I.D., minimum 6" fall per 100', 1500 lb. crush strength or equivalent.
☐ Other

Conveyance method: yes ☒ no ☐ comments
Satisfactory

Distribution box:
Precast concrete with 6 ports.
☒ Other APPROVED VINYL D-BOX

Distribution box: yes ☒ no ☐ comments
Satisfactory TESTED H26

Header lines:
Material: 4" I.D. 1500 lb. crush strength plastic or equivalent from distribution box to 2' into absorption trench. Slope 2" minimum.
☐ Other

Header lines: yes ☒ no ☐ comments
Satisfactory

Percolation lines:
Gravity 4" plastic 1000 lb. per foot bearing load or equivalent, slope 2" 4" (min. max.) per 100'.
☐ Other

Percolation lines: yes ☒ no ☐ comments
Satisfactory
NO REDUCTION IN INFILTRATIONS

Absorption trenches:
Square ft. required 450; depth from ground surface to bottom of trench 30"; aggregate size 1/2" TO 1 1/2"; Trench bottom slope 1/4" PER 10' LINEAR FT.; center to center spacing 9'; trench width 36"; Depth of aggregate 13"; Trench length 50'; Number of trenches 3

Absorption trenches: yes ☒ no ☐ comments
Satisfactory

Date SEE ATTACHED Inspected and approved by:

3H EETS

Sanitarian

Schematic drawing of sewage disposal and/or water supply and topographic features.

Show the lot lines of the building site, sketch of property showing any topographic features which may impact on the design of the well or sewage disposal system, including existing and /or proposed structures and sewage disposal systems and well within 200'. The schematic drawing of the well site or area and/or SDS shall show sewer lines, pretreatment unit, pump station, conveyance system, and subsurface soil absorption system, reserve area, etc. When a nonpublic drinking water supply is to be permitted, show all sources of pollution within 200 feet.

☐ THE INFORMATION REQUIRED ABOVE HAS BEEN DRAWN ON THE ATTACHED COPY OF THE SKETCH SUBMITTED WITH THE APPLICATION. ATTACH ADDITIONAL SHEETS AS NECESSARY TO ILLUSTRATE THE DESIGN.

SEE PERMIT FOR SPECS

NO SUBSTITUTED SYSTEMS ALLOWED WITHOUT PRIOR APPROVAL AND DESIGN BY THE AOSE

CALL Tom King FOR ANY CHANGES NEEDED AND FOR FINAL INSPECTION
639-6765

THIS SEWAGE DISPOSAL SYSTEM AND/OR WATER SUPPLY IS TO BE CONSTRUCTED AS SPECIFIED BY THE PERMIT ☒ OR ATTACHED PLANS AND SPECIFICATIONS ☐.

This sewage disposal system and/or well construction permit is null and void if (a) conditions are changed from those shown on the application (b) conditions are changed from those shown on the construction permit.

No part of any installation shall be covered or used until inspected, corrections made if necessary, and approved, by local health department or unless expressly authorized by the local health dept. Any part of any installation which has been covered prior to approval shall be uncovered, if necessary, upon the direction of the Department.

Date: 5-16-03

Level I Review by: _____


Joe Burch
Environmental Health Specialist

Date: 5-20-03

Level I Review by: _____

Lina Thompson
Environmental Health Supervisor

This Construction Permit
valid until:
11-16-04



AS
INSTALLED
10-22-03

SITE #2

Health Department
 Identification Number _____

Schematic drawing of sewage disposal and/or water supply system and topographic features.

Show the lot lines of the building site, sketch of property showing any topographic features which may impact on the design of the well or sewage disposal system, including existing and/or proposed structures and sewage disposal systems and wells within 200 feet. The schematic drawing of the well site or area and/or sewage disposal system shall show sewer lines, pretreatment unit, pump station, conveyance system, and subsurface soil absorption system, reserve area, etc. When a nonpublic drinking water supply is to be permitted, show all sources of pollution within 200 feet.

☐ The information required above has been drawn on the attached copy of the sketch submitted with the application. Attach additional sheets as necessary to illustrate the design.

① DRAIN FIELD SITE/AREA

(1) BED ROOM DESIGN: (3) LINES, 30' DEEP, 36" WIDE, 9' CENTERS, 50' LONG.

(2) KEEP DRAIN FIELD 5' FROM PROPERTY LINES, 10' FROM HOUSE, 100' FROM WELLS.

(3) INSTALL SEPTIC LINES ON GROUND CONTOUR.

(4) KEEP SEPTIC TANK 50' FROM ALL WELLS, 10' FROM HOUSE, 5' FROM PROPERTY LINES.

(5) GRAVEL SIZE 1/2" TO 1 1/2" CLEAN & CRUSHED STONE.

(6) SEPTIC TANK SIZE 1,000 GALLON WITH INSPECTION PORT.

(7) Cut down all maple trees within 10' of the drainfield area. Do not disturb tree roots prior to drainfield installation.

Soil Evaluation Form

PAGE _____ OF _____

Commonwealth of Virginia
Department of Health

Health Department
Identification Number _____
Tax Map Number 77-19B

General Information

Date 9-16-03 FLOYD CU Health Department
Applicant FRANKLIN D. FORQUER Telephone No. 593-3303
Address 115 HALLS STORE RD, WILLIS, VA. 24380
Owner S Address S
Location INTERSECTION RTS 799 & 604
Subdivision _____ Block/Section TRACT "B" Lot _____

Soil Information Summary

1. Position in landscape satisfactory Yes ☒ No ☐ Describe PARTLY SHADOWED & CLEARED SIDE SLOPE
 2. Slope 10 %
 3. Depth to rock/impervious strata Max. _____ Min. _____ None ☒
 4. Depth to seasonal water table (gray mottling or gray color) No ☒ Yes ☐ _____ inches
 5. Free water present No ☒ Yes ☐ _____ range in inches
 6. Soil percolation rate estimated Yes ☒ Texture group I ☐ II ☒ III ☐ IV
No ☐ Estimated rate 90 min/inch
 7. Percolation test performed Yes ☐ Number of percolation test holes _____
No ☒ Depth of percolation test holes _____
Average percolation rate _____
- Name and title of evaluator: J. A. King, SOIL CONSULTANT & Stone Walter AUSE # 169
Signature: J. A. King & Stone Walter

Department Use

- ☒ Site Approved: Drainfield to be placed at 30" depth at site designated on permit.
☐ Site Disapproved: J.B.
- Reasons for rejection:
1. ☐ Position in landscape subject to flooding or periodic saturation.
 2. ☐ Insufficient depth of suitable soil over hard rock.
 3. ☐ Insufficient depth of suitable soil to seasonal water table.
 4. ☐ Rates of absorption too slow.
 5. ☐ Insufficient area of acceptable soil for required drainfield, and/or Reserve Area.
 6. ☐ Proposed system too close to well.
 7. ☐ Other Specify _____

SITE A2

Date of Evaluation 9-18-03

**Profile Description
SOIL EVALUATION REPORT**

Health Department
Identification No. _____

Page _____ of _____

Where the local health department conducts the soil evaluation the location of profile holes may be shown on the schematic drawing on the construction permit or the sketch submitted with the application. If soil evaluations are conducted by a private soil scientist, location of profile holes and sketch of the area investigated including all structural features i.e., sewage disposal systems, wells, etc., within 100 feet of site (See section 4) and reserve site shall be shown on the reverse side of this page or prepared on a separate page and attached to this form.

☐ See application sketch

☐ See construction permit

☒ See sketch on reverse side or page attached to this form.

ADJACENT

Hole #	Horizon	Depth (Inches)	Description of, color, texture, etc.	Texture Group
1	A	0-7	7.5%N 3/3 DARK BROWN LOAM SOME SLATE SURFACE ROCK	II
	B ₁	7-29	7.5%N 4/6 STAINY BROWN SANDY CLAY LOAM	II
	B ₂	29-40	7.5%N 5/6 STAINY BROWN SANDY CLAY LOAM	II
	B ₃	40-50	10%N 5/8 YELLOWISH-BROWN SANDY CLAY LOAM	II
	B ₄	50-60	10%N 5/8 YELLOWISH-BROWN SANDY LOAM WEATHERED	II
2			SAME CONSISTENT PROFILE HOLE AS NO. 1 HOLE	
3	A	0-6	7.5%N 3/3 DARK BROWN LOAM	II
	B ₁	6-30	7.5%N 4/6 STAINY BROWN SANDY CLAY LOAM WEATHERED MATERIAL	II
	B ₂	30-48	10%N 5/8 YELLOWISH-BROWN SANDY LOAM Manganese concretions at 48"	II
	B ₃	48-60	10%N 5/8 YELLOWISH- BROWN SANDY LOAM MICACEOUS MATERIAL	II

Remarks RECOMMEND DRAIN FIELD DITCHES
DEPTH 30"

Completion Statement

#2 SITE

Commonwealth of Virginia
State Department of Health

GIN 77-14 B

Health Department
Identification Number

03-131-

FLOYD CO

Health Department

Name of Company/Corporation/Individual: ROUND MEADOW ENTERPRISES INC.

Address: 4668 CHERRY CREEK RD. MEADOWS OF DAN, VA. 24120

Telephone: 276-952 2661

Owner's Name FRANKLIN TERQUEA

Owner's Address 11540 L S STONE RD. WILKES, VA 24384

Location of Installation: Lot _____ Block _____

Section: _____ Subdivision: _____

Other: _____

I hereby certify that the onsite sewage disposal system has been installed and completed in accordance with the construction permit issued (date) 5-21-03 and is in compliance with Part D of the Sewage Handling and Disposal Regulations and when appropriate the plans and specifications for the project.

10-22-03

Date

Werner E. B. Pres

Signature and Title

Completion Statement

#2 SITE

Commonwealth of Virginia
State Department of Health

GA 77-14 B

Health Department
Identification Number

03-131-

FLOYD CO

Health Department

Name of Company/Corporation/Individual: ROUND MEADOW ENTERPRISES INC.

Address: 4668 CHERRY CREEK RD. MEADOWS OF DAN, VA. 24120

Telephone: 276-952-2661

Owner's Name FRANKLIN TORQUEA

Owner's Address 115 HILLS STONE RD. WICKES, VA 24380

Location of Installation: Lot _____ Block _____

Section: _____ Subdivision: _____

Other: _____

I hereby certify that the onsite sewage disposal system has been installed and completed in accordance with the construction permit issued (date) 5-21-03 and is in compliance with Part D of the Sewage Handling and Disposal Regulations and when appropriate the plans and specifications for the project.

10-22-03

Date

[Signature]

Signature and Title

677 (F) 2ND SITE

Commonwealth of Virginia
Application for a Sewage Disposal and/or Water Supply Permit

Health Department ID 03-131-4113

W 4-28-03 390 2165603

To Be Completed By The Applicant

Type of Sewage system: ☒ New ☐ Repair ☐ Expanded ☐ Conditional
FHA/VA yes ☐ no ☒ Case No. 115 HALLS STORE RD SW

Owner FRANKLIN D. FORQUER Address WILLIS, VA. 24380 Phone 540-593-3303
EVELYN D. FORQUER

Agent _____ Address _____ Phone _____

Directions of Property INTERSECTION RTS 799 & 604 ON RT 604
FOR 0.1 MI ON RIGHT PRIVATE ENTRANCE.

Subdivision _____ Section _____ Block _____ Lot TRACT "B"

Other Property Identification PARTLY CLEARED & WOODED

Dimension/size of Lot/Property 7.9 ACRES

Other Application Information

I. Building/facility ☒ New ☐ Existing
Intermittent Use ☒ Yes ☐ No If yes, describe _____

II. Residential Use ☒ Yes ☐ No
Termite Treatment ☒ Yes ☐ No
☒ Single Family ☐ Multi-family
(Number of Bedrooms 1) (Number of Units _____)

Basement ☐ Yes ☒ No
Fixtures in Basement ☐ Yes ☒ No

III. Commercial Use ☐ Yes ☐ No Describe: _____
Commercial/Wastewater ☐ Yes ☐ No Number of Patrons _____
Number of Employees _____

If yes, give volumes and describe _____

IV. Water Supply: ☐ Public ☐ New ☐ Existing
☒ Private ☐ New ☒ Existing

Describe: WILL DRILL NEW WELL BETWEEN THE TWO CABINS -
FOR THIS PERMIT!

V. Proposed Sewage Disposal Method:

Onsite Sewage Disposal System: ☒ Septic Tank Drainfield ☒ LPD ☐ Mound ☐ Other

Public Sewerage System

Attach a site plan (rough sketch) showing dimensions of property, proposed and/or existing structures and driveways, underground utilities, adjacent soil absorption system, bodies of water, drainage ways, and wells and springs within 200 feet radius of the center of the proposed well or drainfield. Distances may be paced or estimated.

The property lines and building location are clearly marked and the property is sufficiently visible to see the topography. I give permission to the Department to enter onto the property described for the purpose of processing this application.

Frank Forquer
Signature of Owner/Agent

4-28-03
Date

INSTRUCTIONS FOR WELL & SEPTIC APPLICANTS

SITE #2

Our goal at the Health Department is to process your application as quickly as possible. Sometimes we take longer to process applications because of our workload, the weather, or need for a backhoe to evaluate the soil. These delays are unavoidable. At other times we are delayed because applicants have not provided us with the information we need to process applications quickly. We cannot accept incomplete applications. In order for us to do our job properly, applicants need to provide us with the following:

- A) A complete application, including an accurate site sketch
- B) Clear directions to the property
- C) The property corners and house site must be staked on the property
- D) A copy of a zoning verification letter if required by the county or city.

This checklist is provided to assist you with our application process. All items listed *must be completed by the applicant* before the application will be accepted by the Health Department. If you have questions or need assistance with the application, one of our Environmental Health Staff will be happy to help you.

- A) The application:
 - ☒ has all items properly filled out
 - ☒ has a telephone number or email address where I can be reached during the day
 - ☒ has clear written directions to the property
 - ☒ is signed and dated
 - ☒ is accompanied by the proper fee
- B) The site sketch clearly and accurately shows:
 - ☒ the shape of the property
 - ☒ the length of each property line
 - ☒ the shape and location of the house (including decks and porches)
 - ☒ the proposed location of the driveway
 - ☒ the proposed or existing location of any utilities
 - ☒ any legal easements located on the property
 - ☒ the location of wells, springs, and buried fuel tanks within 200 feet of the property
 - ☒ the location of any other structures I plan to build in the future (e.g. barn, garage, swimming pool)
 - ☒ where I would like my septic system and/or well to be located (if there is a preference)
- C) The building site for which the application is made:
 - ☒ has the property lines clearly and accurately marked
 - ☒ has the house site clearly and accurately marked
 - ☒ has the brush removed from the potential drainfield site
 - ☒ is easily identified from the road
 - ☒ has any underground utilities marked

NOTE: the attached pages have a sample site sketch that may be useful in marking your property and completing your site sketch.

I understand that the Health Department cannot accept incomplete applications and that if the property corners are not clearly marked, the house site properly staked, and the brush cleared from the proposed drainfield site my application will be denied until I have taken corrective actions. I understand that I have ninety days to correct any deficiencies and submit a new application. Failure to do so within the prescribed time frame will require that I submit a new application *with the associated fees*.

I am the current owner (name is on the deed) of the property and intend to begin construction within 18 months- (apply for a permit to install)-

Applicant's Signature THOMAS D. FORBES

Date 4-28-03

I, the undersigned, am interested in purchasing /selling the property provided there is a suitable drainfield site- (apply for certification letter)

Applicant's Signature _____

Date _____

Soil Evaluation Form

PAGE _____ OF _____

Commonwealth of Virginia
Department of HealthHealth Department
Identification Number _____
Tax Map Number 77-19B

General Information

Date 9-16-03 FLOYD CO Health Department
 Applicant FRANKLIN D. FORQUER Telephone No. 593-3303
 Address 115 HALLS STORE RD, WILLIS, VA. 24380
 Owner S Address S
 Location INTERSECTION RTS 799 & 604
 Subdivision _____ Block/Section TRACT "B" Lot _____

Soil Information Summary

1. Position in landscape satisfactory Yes ☒ No ☐ Describe PARTLY SHADOWED & CLEARED SIDE SLOPE
2. Slope 10 %
3. Depth to rock/impervious strata Max. _____ Min. _____ None ☒
4. Depth to seasonal water table (gray mottling or gray color) No ☒ Yes ☐ _____ inches
5. Free water present No ☒ Yes ☐ _____ range in inches
6. Soil percolation rate estimated Yes ☒ Texture group I II III IV
 No ☐ Estimated rate 90 min/inch
7. Percolation test performed Yes ☐ Number of percolation test holes _____
 No ☒ Depth of percolation test holes _____
 Average percolation rate _____
- Name and title of evaluator: J. A. King, FOR CONSULTANT & Stone Walter Assoc # 169
- Signature: J. A. King & Stone Walter

Department Use

- ☐ Site Approved: Drainfield to be placed at _____ depth at site designated on permit.
- ☐ Site Disapproved:

Reasons for rejection:

1. ☐ Position in landscape subject to flooding or periodic saturation.
2. ☐ Insufficient depth of suitable soil over hard rock.
3. ☐ Insufficient depth of suitable soil to seasonal water table.
4. ☐ Rates of absorption too slow.
5. ☐ Insufficient area of acceptable soil for required drainfield, and/or Reserve Area.
6. ☐ Proposed system too close to well.
7. ☐ Other Specify _____

SITE #2

Date of Evaluation 9-18-03

Profile Description SOIL EVALUATION REPORT

Health Department
Identification No. _____

Page _____ of _____

Where the local health department conducts the soil evaluation the location of profile holes may be shown on the schematic drawing on the construction permit or the sketch submitted with the application. If soil evaluations are conducted by a private soil scientist, location of profile holes and sketch of the area investigated including all structural features i.e., sewage disposal systems, wells, etc., within 100 feet of site (See section 4) and reserve site shall be shown on the reverse side of this page or prepared on a separate page and attached to this form.


☐ See application sketch☐ See construction permit☐ See sketch on reverse side or page attached to this form.

AUGER

Hole #	Horizon	Depth (Inches)	Description of, color, texture, etc.	Texture Group
1	A	0-7	7.5%N $\frac{3}{3}$ DARK BROWN LOAM SOME SLATE SURFACE ROCK	II
	B ₁	7-29	7.5%N $\frac{4}{6}$ STAINY BROWN SANDY CLAY LOAM	II
	B ₂	29-40	7.5%N $\frac{5}{8}$ STAINY BROWN SANDY CLAY LOAM	II
	B ₃	40-50	10%N $\frac{5}{8}$ YELLOWISH-BROWN SANDY CLAY LOAM	II
	B ₄	50-60	10%N $\frac{4}{6}$ YELLOWISH-BROWN SANDY LOAM WEATHERED	II
2			SAME CONSISTENT PROFILE HOLE AS NO. 1 HOLE	
3	A	0-6	7.5%N $\frac{3}{3}$ DARK BROWN LOAM	II
	B ₁	6-30	7.5%N $\frac{4}{6}$ STAINY BROWN SANDY CLAY LOAM WEATHERED MATERIAL	II
	B ₂	30-48	10%N $\frac{5}{8}$ YELLOWISH-BROWN SANDY LOAM	II
	B ₃	48-60	10%N $\frac{5}{6}$ YELLOWISH-BROWN SANDY LOAM MICACEOUS MATERIAL	II

Remarks

RECOMMEND DRAIN FIELD DITCHES
DEPTH 30"



7.9 ACRES

NO SCALE

- D-BOX - STAKED,
- FLAGGED, D - FIELD -
- STAKED - FLAGGED,
- TEST HOLES - STAKED
- FLAGGED - WELL -
- SITE - STAKED.
- CABIN SITE
- STAKED.

RT 799 → TO WILLS

SOIL TEST LOCATION
SHEETS 123HS
SHEET SITE #2

STEP 2

Water Supply and/or Sewage Disposal System Construction Permit

Commonwealth of Virginia
Department of Health

Health Department
Identification Number
Map Reference

FLO/D CU Health Department

77-19-B

General Information

Water Supply System: New ☒ Repair ☐ Public ☐ FHA ☐ VA ☐ Case No. ☐
Sewage Disposal System: New ☒ Repair ☐ Expanded ☐ Conditional ☐ Public ☐
Based on the application for a sewage disposal system construction permit filed in accordance with Section 2.13 E, of the Sewage Handling and Disposal Regulations and/or Section 2.13 of the Private Well Regulations a construction permit is hereby issued to:
Owner FRANKLIN D. & EVELYN D. FOR QUER Telephone 593-3303
Address 115 HALLS STORE RD, WILLIS, VA 24380 For a Type I Sewage Disposal System or Well to be constructed on/at INTERSECTION RTE 799 & 604 ON 604 FOR UNION RIGHT-
Subdivision ☐ Section/Block ☐ Lot ☐ Actual or estimated water use 150

DESIGN

Water supply, existing: (describe) TO BE DRILLED BETWEEN THE TWO CABINS
To be installed: class III C PRIVATE
cased 20' grouted 20'

Building sewer:
3" / 4" I.D. PVC Schedule 40, or equivalent.
Slope 1.25" per 10' (minimum).
☐ Other ☐

Septic tank: Capacity 1,000 gals. (minimum).
☒ Other WITH INSPECTION PORT

Inlet-outlet structure:
PVC Schedule 40, 4" tees or equivalent.
☐ Other ☐

Pump and pump station:
No ☒ Yes ☐ describe and show design.
if yes: ☐

Gravity mains: 3" or larger I.D., minimum 6" fall per 100', 1500 lb. crush strength or equivalent.
☐ Other ☐

Distribution box:
Precast concrete with 6 ports.
☒ Other APPROVED VINYL D-BOX

Header lines:
Material: 4" I.D. 1500 lb. crush strength plastic or equivalent from distribution box to 2' into absorption trench. Slope 2" minimum.
☐ Other ☐

Percolation lines:
Gravity 4" plastic 1000 lb. per foot bearing load or equivalent, slope 2" 4" (min. max.) per 100'.
☐ Other ☐

Absorption trenches:
Square ft. required 450; depth from ground surface to bottom of trench 30"; aggregate size 1/2 TO 1 1/2"; Trench bottom slope 1/4 PER 10' LINEAR FT.; center to center spacing 9'; trench width 36"; Depth of aggregate 13; Trench length 50'; Number of trenches 3

NOTE: SEWAGE DISPOSAL SYSTEM INSPECTION RESULTS

Water supply location: Satisfactory yes ☐ no ☐ comments
Completion Report
G. W. 2 Received: yes ☐ no ☐ not applicable ☐

Building sewer: yes ☐ no ☐ comments
Satisfactory

Pretreatment unit: yes ☐ no ☐ comments
Satisfactory

Inlet-outlet structure: yes ☐ no ☐ comments
Satisfactory

Pump & pump station: yes ☐ no ☐ comments
Satisfactory

Conveyance method: yes ☐ no ☐ comments
Satisfactory

Distribution box: yes ☐ no ☐ comments
Satisfactory

Header lines: yes ☐ no ☐ comments
Satisfactory

Percolation lines: yes ☐ no ☐ comments
Satisfactory

Absorption trenches: yes ☐ no ☐ comments
Satisfactory

Date ☐ Inspected and approved by:

Sanitarian

Water Supply and/or Sewage Disposal System Construction Permit

Commonwealth of Virginia

Department of Health

FLO/D CU Health Department

Health Department

Identification Number

Map Reference 77-19-B

General Information

Water Supply System: New ☒ Repair ☐ Public ☐ FHA ☐ VA ☐ Case No. ☐
 Sewage Disposal System: New ☒ Repair ☐ Expanded ☐ Conditional ☐ Public ☐
 Based on the application for a sewage disposal system construction permit filed in accordance with Section 2.13 E, of the Sewage Handling and Disposal Regulations and/or Section 2.13 of the Private Well Regulations a construction permit is hereby issued to:
 Owner FRANKLIN D. & EVELYN D. FOR QUER Telephone 593-3303
 Address 115 HALLS STORE RD, WILLIS, VA 24380 For a Type I Sewage Disposal System or Well to be constructed on/at INTERSECTION RT 799 & 609 ON 609 FOR UNION RIGHT-
 Subdivision ☐ Section/Block ☐ Lot ☐ Actual or estimated water use 150

DESIGN

NOTE: SEWAGE DISPOSAL SYSTEM INSPECTION RESULTS

Water supply, existing: (describe) TO BE DRILLED BETWEEN THE TWO CABINS
 To be installed: class III C PRIVATE
 cased 20' grouted 20'

Water supply location: Satisfactory yes ☐ no ☐ comments
 Completion Report
 G. W. 2 Received: yes ☐ no ☐ not applicable ☐

Building sewer:
3" / 4" I.D. PVC Schedule 40, or equivalent.
 Slope 1.25" per 10' (minimum).
☐ Other

Building sewer: yes ☐ no ☐ comments
 Satisfactory

Septic tank: Capacity 1,000 gals. (minimum).
☒ Other WITH INSPECTION PORT

Pretreatment unit: yes ☐ no ☐ comments
 Satisfactory

Inlet-outlet structure:
 PVC Schedule 40, 4" tees or equivalent.
☐ Other

Inlet-outlet structure: yes ☐ no ☐ comments
 Satisfactory

Pump and pump station:
 No ☒ Yes ☐ describe and show design.
 if yes:

Pump & pump station: yes ☐ no ☐ comments
 Satisfactory

Gravity mains: 3" or larger I.D., minimum 6" fall per 100', 1500 lb. crush strength or equivalent.
☐ Other

Conveyance method: yes ☐ no ☐ comments
 Satisfactory

Distribution box:
 Precast concrete with 6 ports.
☒ Other APPROVED VINYL D-BOX

Distribution box: yes ☐ no ☐ comments
 Satisfactory

Header lines:
 Material: 4" I.D. 1500 lb. crush strength plastic or equivalent from distribution box to 2' into absorption trench. Slope 2" minimum.
☐ Other

Header lines: yes ☐ no ☐ comments
 Satisfactory

Percolation lines:
 Gravity 4" plastic 1000 lb. per foot bearing load or equivalent, slope 2" 4" (min. max.) per 100'.
☐ Other

Percolation lines: yes ☐ no ☐ comments
 Satisfactory

Absorption trenches:
 Square ft. required 450; depth from ground surface to bottom of trench 30"; aggregate size 1/2" to 1 1/2"; Trench bottom slope 1/4" PER 10' LINEAR FT.; center to center spacing 9'; trench width 36"; Depth of aggregate 13"; Trench length 50'; Number of trenches 3

Absorption trenches: yes ☐ no ☐ comments
 Satisfactory

Date Inspected and approved by:

Sanitarian

Water Supply and/or Sewage Disposal System Construction Permit

Commonwealth of Virginia

Department of Health

FLO/D CU Health Department

Health Department

Identification Number

Map Reference 77-19-B

General Information

Water Supply System: New ☒ Repair _____ Public _____ FHA _____ VA _____ Case No. _____
 Sewage Disposal System: New ☒ Repair _____ Expanded _____ Conditional _____ Public _____
 Based on the application for a sewage disposal system construction permit filed in accordance with Section 2.13 E, of the Sewage Handling and Disposal Regulations and/or Section 2.13 of the Private Well Regulations a construction permit is hereby issued to:
 Owner FRANKLIN D. & EVELYN D. FOR QUER Telephone 593-3303
 Address 115 HALLS STORE RD, WILLIS, VA 229 For a Type I Sewage Disposal System or Well to be constructed on/at INTERSECTION PTS 799 & 609 ON 609 FOR 1/4 MILE ON RIGHT
 Subdivision _____ Section/Block _____ Lot _____ Actual or estimated water use 150

DESIGN

NOTE: SEWAGE DISPOSAL SYSTEM INSPECTION RESULTS

Water supply, existing: (describe) TO BE DRILLED BETWEEN THE TWO CABINS
 To be installed: class III C PRIVATE
 cased 20' grouted 20'

Water supply location: Satisfactory yes ☐ no ☐ comments _____

Completion Report

G. W. 2 Received: yes ☐ no ☐ not applicable ☐

Building sewer: 3" / 4" I.D. PVC Schedule 40, or equivalent.
 Slope 1.25" per 10' (minimum).
☐ Other _____

Building sewer: yes ☐ no ☐ comments Satisfactory

Septic tank: Capacity 1000 gals. (minimum).
☒ Other WITH INSPECTION PORT

Pretreatment unit: yes ☐ no ☐ comments Satisfactory

Inlet-outlet structure:
 PVC Schedule 40, 4" tees or equivalent.
☐ Other _____

Inlet-outlet structure: yes ☐ no ☐ comments Satisfactory

Pump and pump station:
 No ☒ Yes ☐ describe and show design. if yes: _____

Pump & pump station: yes ☐ no ☐ comments Satisfactory

Gravity mains: 3" or larger I.D., minimum 6" fall per 100', 1500 lb. crush strength or equivalent.
☐ Other _____

Conveyance method: yes ☐ no ☐ comments Satisfactory

Distribution box:
 Precast concrete with 6 ports.
☒ Other APPROVED VINYL D-BOX

Distribution box: yes ☐ no ☐ comments Satisfactory

Header lines:
 Material: 4" I.D. 1500 lb. crush strength plastic or equivalent from distribution box to 2' into absorption trench. Slope 2" minimum.
☐ Other _____

Header lines: yes ☐ no ☐ comments Satisfactory

Percolation lines:
 Gravity 4" plastic 1000 lb. per foot bearing load or equivalent, slope 2" 4" (min. max.) per 100'.
☐ Other _____

Percolation lines: yes ☐ no ☐ comments Satisfactory

Absorption trenches:
 Square ft. required 450; depth from ground surface to bottom of trench 30"; aggregate size 1/2" to 1 1/2"; Trench bottom slope 1/4" PER 10' LINEAR FT.; center to center spacing 9'; trench width 36"; Depth of aggregate 13"; Trench length 50'; Number of trenches 3

Absorption trenches: yes ☐ no ☐ comments Satisfactory

Date _____ Inspected and approved by: _____

Sanitarian

SITE #2

Health Department
Identification Number _____

Schematic drawing of sewage disposal and/or water supply system and topographic features.

Show the lot lines of the building site, sketch of property showing any topographic features which may impact on the design of the well or sewage disposal system, including existing and/or proposed structures and sewage disposal systems and wells within 200 feet. The schematic drawing of the well site or area and/or sewage disposal system shall show sewer lines, pretreatment unit, pump station, conveyance system, and subsurface soil absorption system, reserve area, etc. When a nonpublic drinking water supply is to be permitted, show all sources of pollution within 200 feet.

☐ The information required above has been drawn on the attached copy of the sketch submitted with the application. Attach additional sheets as necessary to illustrate the design.

① DRAIN FIELD SITE/AREA

(1) BED ROOM DESIGN: (3) LINES, 30' DEEP, 36" WIDE, 9' CENTERS, 50' LONG.


(2) KEEP DRAIN FIELD 5' FROM PROPERTY LINES, 10' FROM HOUSE, 100' FROM WELLS.

(3) INSTALL SEPTIC LINES ON GROUND CONTOUR.

(4) KEEP SEPTIC TANK 50' FROM ALL WELLS, 10' FROM HOUSE, 5' FROM PROPERTY LINES.

(5) GRAVEL SIZE 1/2" TO 1 1/2" CLEAN & CRUSHED STONE.

(6) SEPTIC TANK SIZE 1,000 GALLON WITH INSPECTION PORT.



7.9 ACRES

NO SCALE

RT 799 → to WILLIS

SITE II
2

Certification Statement

County: FLOYD Date: 4-28-03

Property Identification: 7.9 ACRES

Submitted by: P. N. King

This is to certify according to §32.1-163.5 of the Code of Virginia that work submitted for the referred property is in accordance to and complies with the Sewage Handling and Disposal Regulations of the Virginia Department of Health. I recommend a PERMIT¹ be

APPROVED²

AOSE Steve Walton #169 Date: 4-28-03

Soil Consultant: J. N. King Date: 4-28-03

¹ This blank must be filled in with one of the following terms: 'permit', 'certification letter', or 'subdivision approval'.

² This blank must be filled in either the term 'approved' or 'denied'.

If the submission contains a certification by a professional engineer in consultation with an AOSE, the following statement shall be signed and sealed:

I hereby certify that the evaluations and designs contained herein (refer to subdivision, lot, etc.) were conducted in accordance with the Sewage Handling and Disposal Regulations (12 VAC 5-610-10 et seq., the "Regulations") and the policies of the Virginia Department of Health for implementation of those Regulations. Furthermore, I certify that the evaluations and designs comply with the minimum requirements of the Regulations.

I recommend a _____¹ be _____².

Licensed PE: _____ Date: _____

Seal

¹ This blank must be filled in with one of the following terms: 'permit', 'certification letter', or 'subdivision approval'.

² This blank must be filled in either the term 'approved' or 'denied'.

Commonwealth of Virginia
Uniform Water Well Completion Report

Owner Franklin Forquer
Address 115 Stella Stone Rd.
Willis, Va. 24360
Phone 593-3303
Location at intersection of Rtn #799 & 604 1/2 mile on Rght

Tax Map ID 77-1913
VDH Permit 03-131-4114
VM C8 Permit _____
VM C8 ID _____
County Alley

Well Data

General Information

Drilling Method Air Rotary Date Completed 7/24/03 Total Depth of Well 240'
Depth to Bedrock 18' Yield 25 (GPM) Length of Test 1 HR
Static Water Level 26' Stabilized Water Level Und Natural Flow (Rate) Yes
Well Disinfected (Y or N) Yes Disinfectant Used Calcium Hypochlorite Amount Used 22 oz

Casing

From 0' to 28' From _____ to _____ From _____ to _____
Size 6 1/2" ID Material PVC Size _____ Material _____ Size _____ Material _____
Weight/Schedule SCH 80 Weight/Schedule _____ Weight/Schedule _____

Gravel Pack

From 21' to 28' From _____ to _____ From _____ to _____

Grout

From 0' to 21' From _____ to _____ From _____ to _____
Bore Hole Size 10 5/8" Bore Hole Size _____ Bore Hole Size _____
Type Bentonite Gravel Type _____ Type _____
Method Prepacked Pumped Method _____ Method _____

Water Zones or Screened Intervals

From 198' to 199' From _____ to _____ From _____ to _____
Mesh Size _____ Diam. _____ Mesh Size _____ Diam. _____ Mesh Size _____ Diam. _____
From _____ to _____ From _____ to _____ From _____ to _____
Mesh Size _____ Diam. _____ Mesh Size _____ Diam. _____ Mesh Size _____ Diam. _____

Use Data

Private Well: Domestic ☒ Agricultural _____ Industrial _____ Monitoring _____
Public Well: Community _____ Non Community _____

NOV 17 2004

Drillers Log

(Use additional sheets if necessary)

Depth	Description of Formation or Sediment	Remarks
0' - 18'	Silt, Shale, Gravel, Limestone 10 5/8" hole	Bottomite 21' out → 6 1/8"
18' - 28'	Limestone, Quartsy 10 5/8" hole	20' → 6 1/8"
28' - 198'	Limestone, Quartsy 6 1/8" hole	20' → 6 1/8"
198' - 199'	Soft (Water zone 25gpm)	20' → 6 1/8"
199' - 240'	Limestone, Quartsy " "	20' → 6 1/8"
		23' Bottom of Casing Limestone Quartsy 6 1/8"
		198' → 199' Water zone 25gpm
		6 1/8" Limestone Quartsy
		240' Total Depth

I certify that the information contained here is true and that this well was installed and constructed in accordance with the permit and further that the well complies with all applicable state and local regulations, ordinances and laws.

Drilling Contractor U.S. DRILL CO.
 Address 1055 Daniels Run Road NW
 Phone CHECK, VA 24072
540 651-4552
 Drillers Signature Michael N. Wagner Date 8/29/03
 Representing U.S. Drill Co.
 Virginia Contractors License Number 2705-063731

Record of Inspection - Private Water Supply System

Commonwealth of Virginia
Department of Health

Health Department

I.D. Number 03-131-4113 + 4/14

F.H.A. or V.A. Case Number

If Applicable

Date 12-03-2004 Local Health Department FLOYD CO.

Owner Franklin D. Fargher Address 115 Halls Store Rd. Phone 593-3303
Willie VA 24380

Exact Location of Premises Adjacent TO 115 Halls Store Rd. Willie VA 24380

Subdivision 07-24-200341 Section/Block _____ Lot _____

Class of nonpublic drinking water well. 1) Class III A _____

2) Class III B _____

3) Class III C ☒

Date of installation 07-24-2003 4) Other _____

X1-38-47-24
W 80-25-51

CONSTRUCTION INFORMATION

If information in any item below is secured from other sources (i.e. well log, etc.), so note.

1. Water well completion report filed as required by Sec. 2.18 Yes ☐ No ☐
2. Well Location: Distances from sources of pollution (See Table 3.1, Minimum Separation Distances) and Section 3.4 of the Private Well Regulations.
Building Sewer 100' Pretreatment Unit 100'
Conveyance System 100' Subsurface Soil Absorption System 100'
(nearest point). Property Line _____ Other _____
Site graded where necessary to divert water away from well? Yes ☒ No ☐ N/A ☐
3. Construction, General: (see Section 3.6 and 3.7 Private Well Regulations).
Total depth of well 240' feet. Type of casing PVC
Depth of casing 20' feet. Diameter of casing 6 7/8 inches. Bentonite
Casing extends inches above ground 22. Exterior space sealed with neat cement grout to a depth of 21' feet. Screens constructed of _____
free of rough edges and irregularities, with positive watertight seal between screen and casing?
Yes ☐ No ☐ N/A ☐ Well head and opening to the interior protected? Yes ☐ No ☐
Type of well seal approved cap Pitless adapter used? Yes ☐ No ☐ N/A ☐
Properly installed? Yes ☐ No ☐ N/A ☐ Proper venting? Yes ☐ No ☐ N/A ☐
4. Quantity: Yield and drawdown determined by continuous pumping of _____ hours. Drawdown _____ feet. Yield _____ GPM. Type of storage _____
5. Quality: Sample tap provided at entry into system? Yes ☒ No ☐ Samples(s) collected? Yes ☒
No ☐ Results of samples. Satisfactory ☒ Unsatisfactory ☐ (attach copy of results of this form)

Based on the inspection of this water supply system and the information contained on the water well completion report attached, this water supply meets ☒ does not meet ☐ the requirements of the Private Well Regulations.

Remarks: _____

Date 12-03-2004

Signed _____

C. Love Jay
Sanitarian

Date _____

Signed _____

Supervisory Sanitarian

Date _____

Signed _____

Regional Sanitarian (If V.A. or F.H.A.)

FLOYD COUNTY HEALTH DEPARTMENT

**P.O. BOX 157
815 EAST MAIN STREET
FLOYD, VIRGINIA 24091**

October 29, 2004

Mr. & Mrs. Franklin D. Forquer
115 Halls Store Road
Willis, VA 24380

Reference: well and septic permits # 03-131-4113 & 03-131-4114


Dear Mr. & Mrs. Forquer:

According to our records, all of the work has been done at your work site except for the following items. In order to complete your file and issue an operation permit for your well and/or sewage disposal system, we need the following:

- ☒ Well Water Statement (GW-2)
- ☒ Water sample taken (Contact a Virginia State Certified private lab for testing. Make sure the well has been chlorinated at least 1-2 weeks prior to testing.)
- ☒ Well inspection, once well is drilled
- ☐ Completion statement from installer of septic system
- ☐ Approved well cap
- ☐ Other:

Please send us the information requested at your earliest convenience. If you have any questions regarding this matter, you may contact me at the Floyd County Health Department at 540-745-2141.

Sincerely,



Joseph Brunk
Environmental Health Specialist Sr.

SOUTHWEST SOILS LLC
P.O. BOX 90
WOODLAWN, VA 24381

#2 SITE

FLUID CO Health Department

To Whom It May Concern:

On 10-22-03, we inspected the septic system for FRANKLIN & EVELYN FORQUER which is located on tax map parcel/ 77-19B. The system appeared to be in substantial compliance with the permit issued. We recommend an Operation Permit be issued.

Sincerely,

*Stamp: Dallen ACSC #169
By T. H. H. SOIL CONSULTANT*

Southwest Soils

Attachment:

As: Installed Sketch
Permit Checklist

**FLOYD COUNTY HEALTH DEPARTMENT
P.O. BOX 157
815 EAST MAIN STREET
FLOYD, VIRGINIA 24091**

May 21, 2003

Franklin D. and Evelyn D. Forquer
115 Halls Store Road
Willis, VA 24030

Subject: Sewage Disposal System Construction Permit

Dear Mr. and Mrs. Forquer:

This letter, in conjunction with the approved plans (2 pages) dated 05/16/2003, which are attached, constitutes your permit to install a sewage disposal system and well. The application for a permit was submitted pursuant to §32.1-163.5 of the Code of Virginia which requires the Health Department to accept private soil evaluations and designs from an Authorized Onsite Soil Evaluator (AOSE) or a Professional Engineer working in consultation with an AOSE for residential development. The permitted site was certified as being in compliance with the Board of Health's regulations (and local ordinances if the locality has authorized the local health department to accept private evaluations for compliance with local ordinances) by: (Southwest Soils, Inc, LLC; 540-637-4396 or 639-6765). This letter is issued in reliance upon that certification.

The Board of Health hereby recognizes that the soil and site conditions acknowledged by this correspondence, and documented by additional records on file at the local health department, are suitable for the installation of onsite sewage disposal systems. The attached plat (or plats) shows the approved areas for the sewage disposal systems. This letter is void if there is any substantial physical change in the soil or site conditions where a sewage disposal system is to be located.

If modifications or revisions are necessary between now and when you construct your dwelling, please contact the Authorized Onsite Soil Evaluator (AOSE) or Professional Engineer (PE) who performed the evaluation and design on which this permit is based. The name, address and phone number of the AOSE/PE appears on the certification form attached to this permit. Should revisions be necessary during construction, you contractor should consult with the AOSE/PPE that submitted the site evaluation or site evaluation and design. The AOSE or PE is authorized to make minor adjustments in the location or design of the system at the time of construction provided adequate documentation is provided to the Floyd County Health Department.

Franklin D. and Evelyn D. Forquer
May 21, 2003
Page 2

This authorization is null and void if conditions are changed from those shown on the application or conditions are changed from those shown on the attached construction drawings, plans and specifications. No part of any installation shall be covered or used until inspected, corrections made if necessary, and approved by the Floyd County Health Department or unless expressly authorized by the Floyd County Health Department. Any part of any installation which has been covered prior to approval shall be uncovered if necessary, upon the direction of the Department.

This authorization to construct a sewage disposal system expires: 11/16/2004.

Sincerely,



Joseph Brunk
Environmental Health Specialist Senior
Floyd County Health Department

vk